

CODE	DESCRIPTION
S	SOIL – inspect soil conditions, formwork, and reinforcing steel prior to pouring footings.
REB	FOUNDATION REBAR PLACEMENT – inspection of required foundation reinforcing prior to pouring concrete.
OLS	ONTARIO LAND SURVEYOR CERTIFICATE - certificate of lot grading and location of building on site to be submitted prior to foundation system inspection being requested.
FS	FOUNDATION SYSTEMS – inspect weeping tile, crushed stone and all required damp proofing prior to backfill.
SS	SITE SERVICES -
BSBT	BUILDING SEWER BALL TEST – test conducted by plumbing contractor to verify proper grade of main sanitary drain from interior building drain cleanout to property line cleanout.
DWVB	BUILDING DRAINS – BELOW GROUND – verify all size, type and location of drainage and venting pipes, as well as a water or air pressure test to be conducted by plumbing contractor.
IBS	INSULATION BELOW SLAB – verify type and R value of below slab insulation prior to pouring slab.
SLAB	CONCRETE SLAB REINFORCING - inspection of required slab reinforcing prior to pouring concrete.
FM1	FRAMING – PART 9 – inspect all framing materials prior to insulating or covering.
FM2	FRAMING – OTHER THAN PART 9 - inspect all framing materials prior to insulating or covering.
FSC	FIRE SEPERATIONS AND CLOSURES – inspect fire rated components and assemblies.
FP	FIRE PLACE / WOOD STOVE – verify proper clearance to combustibles is provided.
CH	CHIMNEY – verify size, type and location; also verify clearance to combustibles.
HVA1	HVAC ROUGH-IN – PART 9 – inspect all supply, return and exhaust air ducts prior to covering.
HVA2	HVAC ROUGH-IN – OTHER THAN PART 9 - inspect all supply, return and exhaust air ducts prior to covering.
DWVA	DRAINING AND VENTING ABOVE GROUND – verify all size, type and location of drainage and venting pipes, as well as a water or air pressure test to be conducted by plumbing contractor.
AGTI	ABOVE GROUND TIE-INS – verify all size, type and location of drainage and venting pipes – ensure properly tied in to existing.
IB	INSULATION BASEMENT – verify proper R value and vapour barrier installed and sealed prior to covering.
IFF	INSULATION FRAMED FLOOR – verify proper R value and vapour barrier installed and sealed prior to covering.
IW	INSULATION WALLS – verify proper R value and vapour barrier installed and sealed prior to covering.
ICC	INSULATION CATHEDRAL CEILING – verify proper R value and vapour barrier installed and sealed prior to covering.
IRC	INSULATION ROOF AND CEILING – verify proper R value and vapour barrier installed and sealed prior to covering.
DT	DYE TEST – owner/contractor to arrange test with the City of North Bay Public Works Department prior to occupancy of the building.
WDS	WATER DISTRIBUTION SYSTEM – verify proper installation of hot & cold water.
FSM	FIRE SERVICE MAIN -
FPS	FIRE PROTECTION SYSTEMS – verify fire alarm and/or fire suppression systems.
FAR	FIRE ACCESS ROUTES –verify proper size and location of access for firefighting.
PSCS	POOL/SPA CIRC AND RECIRCULATION SYSTEM –
ARC	ARCHITECTURAL FINAL LETTER - final letter of acceptance from Architect.
ELEC	ELECTRICAL FINAL LETTER - final letter of acceptance from Electrical Engineer.
FPL	FIRE PROTECTION FINAL LETTER - final letter of acceptance from Fire Protecting Systems Engineer.
GEO	GEOTECHNICAL FINAL LETTER - final letter of acceptance from Geotechnical Engineer.
MECH	MECHANICAL FINAL LETTER - final letter of acceptance from Mechanical Engineer.
SFL	SEPTIC SYSTEM FINAL LETTER - final inspection certificate from the NBMCA.
STR	STRUCTURAL FINAL LETTER - final letter of acceptance from Structural Engineer.
SPEC	SPECIAL – site/project specific inspection not otherwise listed.
SPCA	SITE PLAN CONTROL AGREEMENT – owner to arrange with City of North Bay Planning Department prior to Notice of Completion.
OPC	OCCUPANCY PRIOR TO COMPLETION – owner wishes to occupy building prior to construction being completed. A \$109 re-inspection fee must be paid prior to occupancy certificate being issued
NOC	COMPLETION OF BUILDING – construction is complete; formal Notice of Completion certificate is issued only if there are no outstanding inspections or fees.

SITE INSPECTION TICKET:

AP – INSPECTION APPROVED AE – MISSED INSPECTION DA – INSPECTION DISAPPROVED
PA – INSPECTION PARTIALLY APPROVED; RE-INSPECTION MAY BE REQUIRED